**EXPANDED SITE PLAN** 

SCALE: 1"= 100'

# SITE & PARCEL DATA

LEGAL DESCRIPTION: TRACT P-801 OF THE PLAT OF "REDMOND RIDGE DIVISION 8 - A MASTER PLAT" AS RECORDED IN VOLUME 208 OF PLATS, PAGES 68 THROUGH 90, INCLUSIVE, UNDER RECORDING NO. 20021001000271, RECORDS OF KING COUNTY, WASHINGTON.

PARCEL NUMBER: 720232-0210

SITE ADDRESS: 22915 NE ALDER CREST DRIVE, REDMOND, WA

TOTAL SITE AREA: 435,642 SQ. FT. (APPROX. 10 ACRES) PROJECT SITE AREA: 2.95 ACRES

AREA IN NATIVE VEGETATION: NO CHANGE FROM ORIGINAL PERMITTED PARCEL BUILT OUT (%): NO CHANGE

SECTION/TOWNSHIP/RANGE: SW-34-26-6

ZONE: UR-P-SO

# **VERTICAL CONTROL AND DATUM TABLE (NAVD 88)**

SOURCE OF DATA: SURVEY CONTROL POINT STANDARD DATA SHEET, PUBLISHED BY THE WGS SURVEY DATA WAREHOUSE

REFERENCE BENCHMARK: POINT DESIGNATION: 836

4" SQUARE CONCRETE MONUMENT WITH 2" BRASS DISK IN A STANDARD MONUMENT CASE IN THE CENTER OF CUL DE SAC ON 220TH PLACE NE ELEVATION: 541.95' (HELD)

ONSITE BENCHMARKS:

POINT DESIGNATION: CONTROL POINT # 1 PK NAIL WITH WASHER STAMPED "DOWL CONTROL", (SEE SHEET C1.0) ELEVATION: 599.90

POINT DESIGNATION: CONTROL POINT # 2 PK NAIL WITH WASHER STAMPED "DOWL CONTROL", (SEE SHEET C1.0) ELEVATION: 600.53

# HORIZONTAL CONTROL AND DATUM TABLE (NAD 83-91)

SOURCE OF DATA: SURVEY CONTROL POINT STANDARD DATA SHEET, PUBLISHED BY THE WGS SURVEY DATA WAREHOUSE

OFFSITE CONTROL POINTS:

POINT DESIGNATION: 836

4" SQUARE CONCRETE MONUMENT WITH 2" BRASS DISK IN A STANDARD MONUMENT CASE IN THE CENTER OF CUL DE SAC ON 220TH PLACE NE NORTHING: 256,432,807 (HELD)

EASTING: 1,341,880.657 (HELD)

POINT DESIGNATION: 1484 4" SQUARE CONCRETE MONUMENT WITH 2" BRASS DISK IN A STANDARD MONUMENT CASE IN THE CENTER OF CUL DE SAC ON 219TH COURT NE NORTHING: 253,534.1467 (HELD)

EASTING: 1,341,479.09 (HELD) NORTHING: 253,533.97 (MEASURED) EASTING: 1,341,479.07 (MEASURED)

ONSITE CONTROL POINTS:

EASTING: 1,344,699.59

POINT DESIGNATION: CONTROL POINT # 4 4" SQUARE CONCRETE MONUMENT WITH 3" BRASS DISK IN A STANDARD MONUMENT CASE AT THE INTERSECTION OF REDMOND RIDGE DRIVE NE AND NE ALDER CREST DRIVE (SEE SHEET C1.0) NORTHING: 254,772.97 EASTING: 1,344,315.44

POINT DESIGNATION: CONTROL POINT # 5 4" SQUARE CONCRETE MONUMENT WITH 2" BRASS DISK IN A STANDARD MONUMENT CASE AT THE INTERSECTION OF REDMOND RIDGE DRIVE NE AND NE 102ND STREET (SEE SHEET C1.0) NORTHING: 253,835.80

# SHEET INDEX

# CIVIL ENGINEERING SHEETS

C2.0 - TESC & DEMO - OVERALL

C4.0 - SITE PLAN - OVERALL

C4.1 - SITE PLAN - NORTH

C5.4 - DRAINAGE DETAILS AND NOTES

L2.0 - FIELD LAYOUT

L3.1 - FENCING DETAILS

L3.2 - DUGOUT DETAILS L4.0 - LANDSCAPE RESTORATION

> KING COUNTY DDES APPROVAL Review Engineer Senior Engineer Molly A. Johnson, P.E. DEVELOPMENT ENGINEER

CO.O - COVER SHEET

CO.1 — GENERAL NOTES C1.0 - EXISTING CONDITIONS - OVERALL

C2.1 - TESC DETAILS

C4.2 - SITE PLAN - SOUTH C4.3 - SITE CIVIL DETAILS & NOTES

C5.0 - GRADING & DRAINAGE - OVERALL

C5.1 - GRADING & DRAINAGE - NORTH

C5.2 - GRADING & DRAINAGE - SOUTH C5.3 - STORM DRAINAGE PROFILES

# LANDSCAPE ARCHITECTURE SHEETS

L1.0 - IRRIGATION RENOVATION - OVERALL

L3.0 - FENCING & PAVEMENT PLAN

Site Plan Approval Scale 1"=2000' Vicinity Map Approval of these plans is for construction of road and drainag improvements, site drainage & grading and temporary erosion control in unincorporated King County only. These plans do not authorize any other utility approval or improvements proposed in any State right of way. Site plan approval is void if the commercial building permit has not been obtained or renewed within two years of approval. Subdivision plan approval is void if the final plat is not recorded prior to the preliminary plat approval expiration. PRO RATA SHARE ASSESSMENT ANALYSIS (County Use Only) Section Township Range Tax Parcel Site Location is within the \_\_\_\_\_ drainage shed(s) Pro Rata Share Assessment(s) are:  $\square$  Required  $\square$  Not Required from the site due to development for increased storm water runoff. Peak Runoff Assessment Rate(\$ ) per c.f.s. increases.(10 year, 2 hour storn Peak Volume Assessment Rate(\$ ) per Ac. Ft. increases.(2 year, 2 hour storn AGREEMENTS, PLAN REFERENCES, PERMITS ETC. (To be completed by Consultant) Scale 1"=2000' Soils Map Preliminary Plat Approval/Permit Issued Date: N/A Expiration Date: Other Related Permit Numbers Received: \_\_\_N/A Right-of-Way Use Permit \_\_\_\_TBD Grading \_\_\_N/A Building/Structural \_\_\_N/A Board feet of tree removal on site: Cubic yards of material hauled on/off the site: \_\_\_\_TBD Is this a highly sensitive area site? (Yes/No): \_\_\_\_NO\_\_\_ Note: If "yes", per SWDM Appendix D44 a Highly Sensitive Site Erosion Control Supervisor is required. See ESC plan.

# Emergency 911

Police-Fire-Rescue

RECOMMENDED FOR APPROVAL (To be completed by King County) Date Review Engineer Senior Engineer Traffic & Planning Engineer Sensitive Areas Structural Review Engineer Other

# King County

APPROVED FOR CONSTRUCTION DEPARTMENT OF DEVELOPMENT & ENVIRONMENTAL SERVICES

Date Molly A. Johnson, P.E. Development Engineer

1. The Developer is required to notify the Land Use Services Division, Land Use Inspection Section (206) 296-6642, three days prior to the beginning of construction for a preconstruction conference and specifically request inspection before beginning: A. Installing siltation and erosion control measures

B. Clearing and grubbing C. Earthwork ). Installation of any underground utility . Before placing subbase, base or paving surfaces

F. Installation of any forms or placing any concrete 2. A permit must be obtained from the office of the Resident Engineer, Washington State Department of Transportation, before any construction

DIAL-A-DIG

Notes

Notice Required

Contractors shall notify operators who maintain underground utility lines in

not more than ten working days prior to commencement of excavation or

demolition in accordance with RCW Title 19. Names and telephone numbers

of the operators of underground utility lines in this project appear below.

required.

CITY OF REDMOND

CITY OF REDMOND

PUGET SOUND ENERGY

PUGET SOUND ENERGY

Call Before You Dig

Sanitary Sewer

Water District

Gas Company

Power Company

These numbers shall also be used to serve in an emergency conditions as

Phone

425-556-2840

425-556-2840

(425) 456-2418

(425) 462-3407

1-800-424-5555

the area of proposed excavation or blasting at least two business days, but

is started on any existing state route. 3. A Hydraulic Project Approval (HPA) Permit must be obtained from the Washington State Department of Fisheries prior to any work when required.

Bonding Information

Restoration Bond Amount Performance Bond Amount \$\_

PROJECT CONTACT INFORMATION (To be completed by Consultant)

REDMOND NORTH LITTLE LEAGUE 206-890-8260 13810 217th PL NE WOODINVILLE WA 98077 ⋈ □ ⋈ Address and Zip Code

☐ An Individual KING COUNTY - PARKS AND 206-734-7248 RECREATION DIVISION Phone Name 201 S. JACKSON ST. SEATTLE, WA 98104 Address and Zip Code

 ■ A Corporation ☐ A Partnership ☐ An Individual

☐ A Partnership

(425) 868-2670DOWL HKM Phone 8420 154TH AVE. NE, REDMOND, 98052 Address and Zip Code

License/Seal

Ш

#### RECOMMENDED CONSTRUCTION SEQUENCE

- . MANDATORY PRE-CONSTRUCTION MEETING WITH OWNER AND KING COUNTY DDES.
- 2. FLAG OR FENCE CLEARING LIMITS.
- 3. POST NOTICE OF CONSTRUCTION ACTIVITY SIGN WITH NAME AND PHONE NUMBER OF ESC SUPERVISOR.
- 4. INSTALL CATCH BASIN PROTECTION IF REQUIRED.
- 5. GRADE AND INSTALL CONSTRUCTION ENTRANCE(S)
- 6. INSTALL PERIMETER PROTECTION (SILT FENCE, BRUSH BARRIER, ETC.).
- 7. CONSTRUCT SEDIMENT PONDS AND TRAPS.
- 8. GRADE AND STABILIZE CONSTRUCTION ROADS.
- 9. CONSTRUCT SURFACE WATER CONTROLS (INTERCEPTOR DIKES, PIPE SLOPE DRAINS, ETC.) SIMULTANEOUSLY WITH CLEARING AND GRADING FOR PROJECT DEVELOPMENT.
- 10. MAINTAIN EROSION CONTROL MEASURES IN ACCORDANCE WITH KING COUNTY STANDARDS AND MANUFACTURER'S RECOMMENDATIONS.
- 11. RELOCATE SURFACE WATER CONTROLS AND EROSION CONTROL MEASURES TEMPORARY STOCKPILE NOTES OR INSTALL NEW MEASURES SO THAT AS SITE CONDITIONS CHANGE THE EROSION AND SEDIMENT CONTROL IS ALWAYS IN ACCORDANCE WITH THE KING COUNTY EROSION AND SEDIMENT CONTROL STANDARDS.
- 12. COVER ALL AREAS THAT WILL BE UNWORKED FOR MORE THAN SEVEN DAYS DURING THE DRY SEASON OR TWO DAYS DURING THE WET SEASON WITH STRAW, WOOD FIBER MULCH, COMPOST, PLASTIC SHEETING OR EQUIVALENT.
- 13. STABILIZE ALL AREAS THAT REACH FINAL GRADE WITHIN SEVEN DAYS.
- 14. SEED OR SOD ANY AREAS TO REMAIN UNWORKED FOR MORE THAN 30
- 15. UPON COMPLETION OF THE PROJECT, ALL DISTURBED AREAS MUST BE STABILIZED AND BEST MANAGEMENT PRACTICES MAY BE REMOVED AS APPROPRIATE.

### **EROSION AND SEDIMENTATION CONTROL NOTES**

- APPROVAL OF THIS EROSION AND SEDIMENT CONTROL (ESC) PLAN DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT ROAD OR DRAINAGE DESIGN (E.G., SIZE AND LOCATION OF ROADS, PIPES, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES, ETC.)
- 2. THE IMPLEMENTATION OF THESE ESC PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR/ESC SUPERVISOR UNTIL ALL CONSTRUCTION IS APPROVED.
- 3. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED BY A CONTINUOUS LENGTH OF SURVEY TAPE (OR FENCING, IF REQUIRED) PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE CLEARING LIMITS SHALL BE PERMITTED. THE CLEARING LIMITS SHALL BE MAINTAINED BY THE CONTRACTOR/ESC SUPERVISOR FOR THE DURATION OF CONSTRUCTION.
- 4. THE ESC FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED PRIOR TO OR IN CONJUNCTION WITH ALL CLEARING AND GRADING SO AS TO ENSURE THAT THE TRANSPORT OF SEDIMENT TO SURFACE WATERS, DRAINAGE SYSTEMS, AND ADJACENT PROPERTIES IS MINIMIZED.
- 5. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE ANTICIPATED MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND MODIFIED TO ACCOUNT FOR CHANGING SITE CONDITIONS (E.G., ADDITIONAL SUMP PUMPS, RELOCATION OF DITCHES AND SILT FENCES, ETC.).
- 6. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR/ESC SUPERVISOR AND MAINTAINED TO ENSURE CONTINUED PROPER FUNCTIONING. WRITTEN RECORDS SHALL BE KEPT OF WEEKLY REVIEWS OF THE ESC FACILITIES DURING THE WET SEASON (OCT. 1 TO APRIL 30) AND OF MONTHLY REVIEWS DURING THE DRY SEASON (MAY 1 TO SEPT. 30).
- 7. ANY AREAS OF EXPOSED SOILS, INCLUDING ROADWAY EMBANKMENTS, THAT WILL NOT BE DISTURBED FOR TWO DAYS DURING THE WET SEASON OR SEVEN DAYS DURING THE DRY SEASON SHALL BE IMMEDIATELY STABILIZED WITH THE APPROVED ESC METHODS (E.G., SEEDING, MULCHING, PLASTIC COVERING, ETC.).
- 8. ANY AREA NEEDING ESC MEASURES NOT REQUIRING IMMEDIATE ATTENTION SHALL BE ADDRESSED WITHIN FIFTEEN (15) DAYS.
- 9. THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN FORTY-EIGHT (48) HOURS FOLLOWING A STORM EVENT.
- 10. AT NO TIME SHALL MORE THAN ONE (1) FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT-LADEN WATER INTO THE DOWNSTREAM SYSTEM.
- 11. STABILIZED CONSTRUCTION ENTRANCES AND ROADS SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES, SUCH AS WASH PADS, MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT. ADDITIONAL QUARRY SPALLS SHALL BE PROVIDED AND PLACED AS NECESSARY TO MAINTAIN PROPER FUNCTION OF CONSTRUCTION ENTRANCES.
- 12. ANY PERMANENT FLOW CONTROL FACILITY USED AS A TEMPORARY SETTLING BASIN SHALL BE MODIFIED WITH THE NECESSARY EROSION CONTROL MEASURES AND SHALL PROVIDE ADEQUATE STORAGE CAPACITY. IF THE FACILITY IS TO FUNCTION ULTIMATELY AS AN INFILTRATION SYSTEM, THE TEMPORARY FACILITY MUST BE GRADED SO THAT THE BOTTOM AND SIDES ARE AT LEAST THREE FEET ABOVE THE FINAL GRADE OF THE PERMANENT FACILITY.
- 13. WHERE STRAW MULCH FOR TEMPORARY EROSION CONTROL IS REQUIRED, 14. TRUCK AND VEHICULAR WHEEL WASHES SHALL BE REQUIRED IF DEEMED IT SHALL BE APPLIED AT A MINIMUM THICKNESS OF 2 TO 3 INCHES.
- 14. PRIOR TO THE BEGINNING OF THE WET SEASON (OCT. 1), ALL DISTURBED AREAS SHALL BE REVIEWED TO IDENTIFY WHICH ONES CAN BE SEEDED IN PREPARATION FOR THE WINTER RAINS. DISTURBED AREAS SHALL BE SEEDED WITHIN ONE WEEK OF THE BEGINNING OF THE WET SEASON. A SKETCH MAP OF THOSE AREAS TO BE SEEDED AND THOSE AREAS TO REMAIN UNCOVERED SHALL BE SUBMITTED TO THE DDES INSPECTOR. THE DDES INSPECTOR CAN REQUIRE SEEDING OF ADDITIONAL AREAS IN ORDER TO PROTECT SURFACE WATERS, ADJACENT PROPERTIES. OR DRAINAGE FACILITIES.

# **EROSION AND SEDIMENTATION CONTROL NOTES (CONT.)**

15. ALL PUBLIC AND PRIVATE ROADS AFFECTED BY THE PROJECT SHALL BE CLEANED ON A REGULAR BASIS. FLUSHING WITH WATER IS NOT ALLOWED.

#### SUPPLEMENTAL ESC NOTES

- . TEMPORARY STOCKPILE NOTES DO NOT APPLY TO THE PROPOSED SHORT-TERM STOCKPILE AND EMBANKMENT AREAS OF THIS PROJECT. SHORT-TERM STOCKPILE AND EMBANKMENT AREAS SHALL BE SEEDED OR OTHERWISE APPROPRIATELY STABILIZED AS NECESSARY TO MEET ESC
- 2. BECAUSE THE SITE IS FLAT AND UNDERLAIN BY HIGHLY INFILTRATIVE SOILS. CONSTRUCTION OF INTERCEPTOR SWALES/DIKES WITH ROCK CHECK DAMS SHALL BE USED ONLY IF SITE STORMWATER BEGINS TO POND OR OTHERWISE DEGRADES SITE CONDITIONS SUCH THAT OTHER WORK OR SURROUNDING AREAS MIGHT BE ADVERSELY AFFECTED.
- 3. CLEARING LIMITS ARE DEFINED BY THE SHOWN LOCATIONS AND ALIGNMENTS OF TEMPORARY SITE FENCE AND SILT FENCE.
- 4. CONTRACTOR IS ESPONSIBLE FOR FINALIZING THE DEPARTMENT OF ECOLOGY SWPPP AND MEETING ALL ECOLOGY PROJECT REQUIREMENTS.

THESE TEMPORARY STOCKPILE NOTES DO NOT APPLY TO SHORT-TERM, ORGANIC MATERIAL STOCKPILE AND PROPOSED SITE EMANKMENTS. OTHER TEMPORARY STOCKPILING MAY BE PERMITTED IF THE FOLLOWING CONDITIONS ARE MET:

- A SIGNIFICANT AMOUNT OF MATERIAL WOULD BE REQUIRED TO BE REMOVED FROM THE SITE, AND THEN RETURNED, CAUSING IMPACTS TO
- THE MATERIAL CAN BE STORED ONSITE IN AN AREA PLANNED FOR LATER CLEARING.
- 3. EACH TEMPORARY STOCKPILE LOCATION (SITE) HAS A SLOPE OF 10% OR
- 4. THE TEMPORARY STOCKPILE WILL HAVE MINIMUM, OR APPROVED, VISUAL IMPACT ON THE SURROUNDING AREA. PROXIMITY OF PUBLIC AREAS TO TEMPORARY STOCKPILE AREA WILL DETERMINE THE SIZE AND HEIGHT PERMITTED. NO TEMPORARY STOCKPILING OVER 8 FEET WILL BE PERMITTED.
- 5. STOCKPILE WILL BE TEMPORARY. DURATION NOT TO EXCEED PERMITTED CONSTRUCTION ACTIVITY.
- 6. TEMPORARY STOCKPILE AREAS SHALL BE COVERED WITH VISQUEEN PLASTIC (MINIMUM 6 MIL) WHEN NOT IN USE. VISQUEEN IS TO BE HELD DOWN BY A MINIMUM OF 10 LB. SAND BAGS PLACED ON A 15-FOOT GRID AND ALONG THE EDGES OF THE PILE.

### **CLEARING AND GRADING NOTES**

- ALL CLEARING AND GRADING WORK SHALL MEET THE REQUIREMENTS OF THE 2009 EDITION OF THE KING COUNTY SURFACE WATER DESIGN MANUAL.
- A PRECONSTRUCTION MEETING SHALL BE HELD WITH THE COUNTY CONSTRUCTION DIVISION, AND ALL REQUIRED PERMITS MUST BE APPROVED PRIOR TO START OF CONSTRUCTION.
- TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE INSTALLED AND PROPERLY OPERATING PRIOR TO ANY GRADING OR EXTENSIVE LAND CLEARING. THESE CONTROLS MUST BE SATISFACTORILY MAINTAINED AND AUGMENTED UNTIL CONSTRUCTION AND LANDSCAPING ARE COMPLETE AND THE PROJECT SITE HAS BEEN STABILIZED.
- DEPENDING UPON SITE AND WEATHER CONDITIONS, ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY THE COUNTY CONSTRUCTION INSPECTOR. WORK PERFORMED DURING THE RAINY SEASON, OCTOBER 1ST THROUGH APRIL 30TH, SHALL REQUIRE A PHASING PLAN TO LIMIT THE EXTENT OF SOIL EXPOSURE AND SHALL BE PERFORMED ACCORDING TO THE REQUIREMENTS OF AN APPROVED PROJECT WET WEATHER PLAN.
- AT THE DISCRETION OF THE COUNTY, WORK MAY BE SUSPENDED DURING PERIODS OF INCLEMENT WEATHER TO REDUCE ACTUAL OR POTENTIAL EROSION AND/OR SEDIMENTATION.
- 6. WHEN WORK IS STOPPED OR COMPLETED IN AN AREA, THE COUNTY CONSTRUCTION INSPECTOR MAY REQUIRE ADDITIONAL EROSION CONTROL, INCLUDING SEEDING, OTHER STABILIZING MEASURES, AND/OR OTHER
- 7. ALL WATER RUNOFF FROM ANY CONSTRUCTION SITE BEING DISCHARGED TO A PUBLIC STORMWATER SYSTEM SHALL NOT EXCEED A TURBIDITY LIMIT VALUE OF 50 NTU'S, AND SHALL ALSO MEET THE REQUIREMENTS OF THE CLEAN WATERS ACT 1972, WASHINGTON ADMINISTRATIVE CODE 173, AND RCW 90.48.
- LOCATIONS OF EXISTING UTILITIES AS SHOWN ARE BASED UPON INFORMATION PROVIDED BY OTHERS AND SHALL BE CONSIDERED APPROXIMATE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACTUAL EXACT LOCATIONS TO AVOID DAMAGE, INJURY, AND/OR DISTURBANCE.
- CONTRACTOR SHALL MAINTAIN OFF-SITE STREETS CLEAN AT ALL TIMES. FLUSHING STREETS SHALL NOT BE ALLOWED. CLEANING OF IMPACTED STREETS SHALL BE VIA SWEEPING.

10. ALL GROUND COVER IS TO REMAIN UNDISTURBED OUTSIDE OF CLEARING

11. FLOWS FROM IMPERVIOUS SURFACES (ROOF, STREETS, DRIVEWAYS, ETC.) SHALL BE CONNECTED TO A DRAINAGE SYSTEM AS SOON AS POSSIBLE. 12. CLEARING LIMITS SHALL BE FIELD LOCATED AND FENCED WITH A

MINIMUM 36-INCH HIGH ORANGE SAFETY FENCE SUPPORTED BY WOOD

13. TREES TO REMAIN (SEE SITE CLEARING, VEGETATION AND MITIGATION PLAN) SHALL BE MARKED WITH FLAGGING, AND FENCED AT 5 FEET OUTSIDE OF THE DRIP LINE WHEN ADJACENT TO AREAS TO BE CLEARED.

OR METAL POSTS.

SEE DETAIL ON SHEET C1.03.

- NECESSARY BY THE COUNTY.
- 15. EXACT ALIGNMENTS AND LOCATIONS OF TESC MEASURES SHOWN ON THE PLANS MAY BE ADJUSTED IN THE FIELD TO ACCOMMODATE PHASING AND CONSTRUCTION SEQUENCE AND PROGRESS, PROVIDED THE REQUIREMENTS AND INTENT OF THIS PLAN AND APPLICABLE JURISDICTIONAL REQUIREMENTS ARE MET.

#### SEASONAL SUSPENSION PLAN NOTES (OCTOBER 1ST THROUGH APRIL 30TH)

THE FOLLOWING NOTES APPLY TO THE PROJECT WHEN WORK CAN NOT PROCEED AND MEET PROJECT ESC REQUIREMENTS, OR IF PROJECT WORK IS TO BE STOPPED AND NOT RESUMED UNTIL THE RAINY SEASON. WORK MAY PROCEED IN THE RAINY SEASON PROVIDED ALL ESC REQUIREMENTS ARE

- ALL UTILITY WORK IN PROGRESS SHALL BE CAPPED AND TRENCHES BACKFILLED.
- 2. ALL EXCAVATION OR FILL WORK SHALL CEASE, PROVIDED CUT AND FILL SLOPE GRADIENTS ARE WITHIN DESIGN GUIDELINES, IF NOT THEY WILL BE QUICKLY CORRECTED PRIOR TO CESSATION OF WORK.
- 3. ALL EXPOSED SOILS. INCLUDING STOCKPILES. SHALL BE STABILIZED UTILIZING A MINIMUM OF 4-INCHES OF MULCH, VISQUEEN, EROSION CONTROL BLANKETS OR A COMBINATION OF THESE METHODS AS SUITABLE FOR THE CONDITIONS.
- 4. OPEN EXCAVATIONS, WHERE WATER COULD ACCUMULATE OVER 18" DEPTH, SHALL BE SURROUNDED BY ADDITIONAL SAFETY FENCING IN ADDITION TO THE FENCING AROUND THE SITE PERIMETER FENCING.
- 5. IF ALL WORK IS SUSPENDED, TEMPORARY MEASURES SHALL BE IMPLEMENTED TO STABILIZE ALL UNCOMPLETED PORTIONS OF STRUCTURES FROM COLLAPSE OR OTHER DAMAGE.

# <u>DEWATERING</u>

- WATER WILL ACCUMULATE IN THE STILLING BASIN OR THE STILLING BASIN EXCAVATION.
- 2. WITH ONSITE SOIL STABILIZED, AND HIGHLY INFILTRATIVE, LITTLE OR NO TURBIDITY IS ANTICIPATED. THE PERMANENT OUTFALL FROM THE FILTER SWALE SYSTEM WILL BE UTILIZED.

#### <u>MAINTENANCE</u>

- THE BMP'S SHALL BE INSPECTED WEEKLY AS WELL AS DURING AND AFTER ANY MAJOR STORM EVENT.
- 2. ANY NECESSARY CORRECTIONS TO THE BMP'S SHALL BE IMPLEMENTED WITHIN 24 HOURS OF THE INSPECTION.
- 3. IN THE EVENT THAT WATER IS LEAVING THE SITE IN EXCESS 50 NTU'S OR IN EXCESS OF 5 NTU'S ABOVE BACKGROUND TURBIDITY, OR HAVE IN EXCESS OF 10% INCREASE WHERE THE BACKGROUND EXCEEDS 50 NTU'S, IMMEDIATE ACTION SHALL BE TAKEN BY THE CONTRACTOR TO CORRECT THE CONDITION. THAT ACTION SHALL INCLUDE PUMPING FLOWS INTO A PASSIVE FILTRATION SYSTEM.

#### **GENERAL CLEARING AND DEMOLITION NOTES**

- 1. READ ALL NOTES AND REVIEW ENTIRE PLAN SET PRIOR TO COMMENCEMENT OF WORK ACTIVITIES.
- 2. ESTABLISH EXACT PROJECT BOUNDARIES PRIOR TO COMMENCEMENT OF WORK, AND RECONFIRM BOUNDARY LINES WHEN COORDINATING WITH NEIGHBORING PROPERTY OWNERS.
- 3. NO EXCAVATION, GRADING OR OTHER SOIL DISTURBING ACTIVITIES SHALL BE PERFORMED UNTIL THE PROJECT GRADING PERMIT HAS BEEN ISSUED AND ALL TESC MEASURES HAVE BEEN COMPLETELY INSTALLED.
- 4. UTILITIES SHOWN IN THIS DRAWING SET ARE BASED ON INFORMATION PROVIDED BY OTHERS. INFORMATION SHOWN SHALL BE CONSIDERED APPROXIMATE AND INCOMPLETE. CONTRACTOR SHALL VERIFY ALL UTILITY LOCATIONS PRIOR TO COMMENCEMENT OF WORK ACTIVITIES.
- 5. ORDINATE ALL APPLICABLE WORK ACTIVITIES WITH APPROPRIATE REPRESENTATIVES OF ADJACENT NEIGHBOR PROPERTIES. OBTAIN PERMISSIONS AS NECESSARY TO PROPERLY AND SAFELY COMPLETE WORK. PROTECT NEIGHBOR PROPERTY AND ITEMS FROM DAMAGE DUE TO PROJECT RELATED EVENTS AND ACTIVITIES.
- 6. PROTECT ALL TESC FEATURES, ITEMS, AND SYSTEMS FROM DAMAGE. MAINTAIN THEIR PROPER FUNCTION THROUGHOUT THE PROJECT.
- 7. COORDINATE STOCKPILE LOCATIONS WITH OWNER. SECURELY COVER STOCKPILES WITH PLASTIC SHEETING. SECURE ALL STOCKPILE COVERS AGAINST WIND, RAIN, AND OTHER DISTURBANCE BY THE ELEMENTS AND/OR OTHER FORCES.
- 8. REMOVE ALL LANDSCAPING ITEMS AND VEGETATION NOT INDICATED FOR RETENTION. REMOVE ALL OTHER MISCELLANEOUS ITEMS, INCLUDING BUT NOT LIMITED TO FENCE POSTS, WOOD, METAL, FENCING, RUBBISH, AND OTHER WASTE ITEMS.
- ). MAINTAIN FULL OPERATION OF PUBLIC ROADWAYS. KEEP CLEAN AND FREE OF DEBRIS, DIRT, AND OTHER PROJECT RELATED ITEMS. SWEEP AS NEEDED TO MEET PROJECT REQUIREMENTS. COORDINATE WITH OWNER AND KING COUNTY ALL DISRUPTIONS TO SERVICES. REPAIR ALL DAMAGE TO MATCH EXISTING CONDITIONS.
- 10. GRADE SITE SUBGRADE TO BE UNIFORMLY AND EVENLY GRADED SUCH THAT POSITIVE AND CONTROLLED DRAINAGE IS MAINTAINED IN ACCORDANCE WITH THE PROJECT TESC (SWPP) PLAN AND THE PROJECT GRADING PLAN.
- 11. REMOVE FROM THE SITE AND PROPERLY DISPOSE OF ALL PROJECT WASTES, SPOILS, AND RUBBISH IN FULL COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS. OBTAIN ALL PERMITS NECESSARY FOR PROPER AND LEGAL DISPOSAL.
- 12. CONTRACTOR IS RESPONSIBLE FOR CONTRACTOR'S OWN QUANTITY

## STRUCTURAL NOTES


- THESE PLANS ARE APPROVED FOR STANDARD ROAD AND DRAINAGE IMPROVEMENTS ONLY. PLANS FOR STRUCTURES SUCH AS BRIDGES, VAULTS, AND RETAINING WALLS REQUIRE A SEPARATE REVIEW AND APPROVAL BY DDES PRIOR TO CONSTRUCTION (KCC 16.04. 16.70, 14.20).
- 2. ROCKERIES ARE CONSIDERED TO BE A METHOD OF BANK STABILIZATION AND EROSION CONTROL. ROCKERIES SHALL NOT BE CONSTRUCTED TO SERVE AS RETAINING WALLS. ALL ROCKERIES IN COUNTY ROAD RIGHT-OF-WAY SHALL BE CONSTRUCTED IN ACCORDANCE WITH KCRS DRAWING NUMBERS 5-004, 5-005, 5-006, AND 5-007. ROCKERIES OUTSIDE OF ROAD RIGHT-OF-WAY SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE UNIFORM BUILDING CODE ...

#### KING COUNTY (DDES) GENERAL NOTES

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE KING COUNTY CODE (KCC), KING COUNTY ROAD STANDARDS (KCRS), KING COUNTY SURFACE WATER DESIGN MANUAL (KCSWDM) AND THE CONDITIONS OF PRELIMINARY SUBDIVISION APPROVAL. IT SHALL BE THE SOLE RESPONSIBILITY OF THE APPLICANT AND THE PROFESSIONAL CIVIL ENGINEER TO CORRECT ANY ERROR, OMISSION, OR VARIATION FROM THE ABOVE REQUIREMENTS FOUND IN THESE PLANS. ALL CORRECTIONS SHALL BE AT NO ADDITIONAL COST OR LIABILITY TO KING COUNTY.
- 2. THE DESIGN ELEMENTS WITHIN THESE PLANS HAVE BEEN REVIEWED ACCORDING TO THE KING COUNTY DEPARTMENT OF DEVELOPMENT AND ENVIRONMENTAL SERVICES (DDES) ENGINEERING REVIEW CHECKLIST. SOME ELEMENTS MAY HAVE BEEN OVERLOOKED OR MISSED BY THE DDES PLAN REVIEWER. ANY VARIANCE FROM ADOPTED STANDARDS IS NOT ALLOWED UNLESS SPECIFICALLY APPROVED BY KING COUNTY PRIOR TO CONSTRUCTION.
- 3. APPROVAL OF THIS ROAD, GRADING, AND DRAINAGE PLAN DOES NOT CONSTITUTE AN APPROVAL OF ANY OTHER CONSTRUCTION (E.G., DOMESTIC WATER CONVEYANCE, SEWER CONVEYANCE, GAS, ELECTRICAL, ETC.).
- 4. BEFORE ANY CONSTRUCTION OR DEVELOPMENT ACTIVITY, A PRECONSTRUCTION MEETING MUST BE HELD BETWEEN THE DDES LAND USE INSPECTION SECTION, THE APPLICANT, AND THE APPLICANT'S CONSTRUCTION REPRESENTATIVE.
- 5. A COPY OF THESE APPROVED PLANS MUST BE ON THE JOB SITE WHENEVER CONSTRUCTION IS IN PROGRESS.
- 6. CONSTRUCTION NOISE SHALL BE LIMITED IN ACCORDANCE WITH KING COUNTY CODE (SECTION 12.88); NORMALLY, THIS IS 7A.M. TO 10 P.M. ON WEEKDAYS AND 9 A.M. TO 10 P.M. ON WEEKENDS.
- IT SHALL BE THE APPLICANT'S/CONTRACTOR'S RESPONSIBILITY TO OBTAIN ALL CONSTRUCTION EASEMENTS NECESSARY BEFORE INITIATING OFF-SITE WORK WITHIN THE ROAD RIGHT-OF-WAY.
- 8. FRANCHISED UTILITIES OR OTHER INSTALLATIONS THAT ARE NOT SHOWN ON THESE APPROVED PLANS SHALL NOT BE CONSTRUCTED UNLESS AN APPROVED SET OF PLANS THAT MEETS ALL REQUIREMENTS OF KCRS CHAPTER 8 IS SUBMITTED TO THE DDES LAND USE INSPECTION SECTION THREE DAYS PRIOR TO CONSTRUCTION.
- 9. DATUM SHALL BE 1988 UNLESS OTHERWISE APPROVED BY DDES.
- 10. GROUNDWATER SYSTEM CONSTRUCTION SHALL BE WITHIN A RIGHT-OF-WAY OR APPROPRIATE DRAINAGE EASEMENT, BUT NOT UNDERNEATH THE ROADWAY SECTION. ALL GROUNDWATER SYSTEMS MUST BE CONSTRUCTED IN ACCORDANCE WITH SECTION B1 3.02 OF THE APWA STANDARD SPECIFICATIONS.
- 11. ALL UTILITY TRENCHES SHALL BE BACKFILLED AND COMPACTED TO 95 PERCENT DENSITY.
- 12. ALL ROADWAY SUBGRADE SHALL BE BACKFILLED AND COMPACTED TO
- 13. OPEN CUTTING OF EXISTING ROADWAYS IS NOT ALLOWED UNLESS SPECIFICALLY APPROVED BY DDES AND NOTED ON THESE APPROVED PLANS. ANY OPEN CUT SHALL BE RESTORED IN ACCORDANCE WITH KCRS 8.03(B)3.

95 PERCENT DENSITY (WSDOT 2-06.3).

14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE SAFEGUARDS, SAFETY DEVICES, PROTECTIVE EQUIPMENT, FLAGGERS, AND ANY OTHER NEEDED ACTIONS TO PROTECT THE LIFE, HEALTH, AND SAFETY OF THE PUBLIC, AND TO PROTECT PROPERTY IN CONNECTION WITH THE PERFORMANCE OF WORK COVERED BY THE CONTRACTOR. ANY WORK WITHIN THE TRAVELED RIGHT-OF-WAY THAT MAY INTERRUPT NORMAL TRAFFIC FLOW SHALL REQUIRE AT LEAST ONE FLAGGER FOR EACH LANE OF TRAFFIC AFFECTED. SECTION 1-07.23, TRAFFIC CONTROL, OF THE WSDOT STANDARD SPECIFICATIONS SHALL APPLY IN ITS ENTIRETY.



S  $\Delta$  $\bigcirc$ Ш C Ш

RD

Ш


Z

Ш

PROJECT 11/30/201

© DOWLHKM 2013 CALL 48 HOURS SHEET **BEFORE YOU DIG** 

1-800-424-5555




SYMBOL	DESC	SIZE	ELEV
1049	DESC D CB	RIM	594.69
1049	IE NW	12"CPEP	591.49
1148	D CB	RIM	
[1170]	D MH	RIM	586.78
[1170]		8"PVC	596.31
_	IE N		588.69
[1203]	IE SW	8"PVC	588.59
[1203]	D YD	RIM	596.99
[4000]	IE SW	6"PVC	595.96
1206	D CB	RIM	596.42
<u> </u>	IE NE	6"PVC	594.28
	IE SW	8"PVC	594.17
1213	D CB	RIM	597.23
	IE NW	8"PVC	594.41
1226	D MH	RIM	588.39
	IE NE	12"PVC	579.14
	IE SW	18"PVC	578.59
1230	D MH	RIM	593.79
	IE NE	8"PVC	586.69
L	IE SW	12"PVC	586.34
	IE NW	8"CONC	589.09
1230	D MH	RIM	593.79
	IE NE	8"PVC	586.69
	IE SW	12"PVC	586.34
	IE NW	8"CONC	589.09
1248	D CB	RIM	593.72
	IE W	6"PVC	590.72
	IE S	8"PVC	590.63
1491	D MH	RIM	599.65
	IE N	8"PERF	594.35
	IE NE	8"PVC	589.55
	IE SE	8"PVC	589.64
	IE NW	12"CPEP	589.20
1652	D CB	RIM	599.50
	IE N	8"PVC	593.60
	IE E	6"PVC	593.60
1662	D MH	RIM	591.41
	IE SW	12"CPEP	581.29
<u> </u>	IE W	12"CPEP	580.74
[1681]	D MH	RIM	590.30
	IE S	8"PVC	586.30
1682	D CB	RIM	593.36



CONVERSION

13427.01 11/30/2012



## PROJECT TESC AND DEMOLITION PLAN NOTES

- 1. COMPLY WITH ALL KING COUNTY CONSTRUCTION REQUIREMENTS.
- 2. UTILITIES AND OTHER FEATURES SHOWN ON THESE PLANS ARE BASED ON SURVEY AND RECORD INFORMATION. CONTRACTOR SHALL ASSUME
- 3. FIELD VERIFY EXACT LOCATIONS OF ALL UTILITIES AND SITE ITEMS.

- 6. COORDINATE ALL UTILITY WORK WITH BOTH UTILITY PURVEYOR AND
- 7. PROVIDE 5-BUSINESS DAYS NOTICE OF ANY SERVICE AND OR ACCESS DISRUPTIONS TO OWNER AND/OR ANY POTENTIALLY AFFECTED
- 8. MAINTAIN GOOD SITE HOUSEKEEPING.
- 9. REPAIR ALL DAMAGE RELATED TO WORK ACTIVITIES, TO MATCH
- 10. ALL DISTURBED LANDSCAPE AREAS THAT ARE NOT INCLUDED IN PROJECT SPECIFIC LANDSCAPING PLANS SHALL BE SCRAPED TO 6-INCHES BELOW FINAL FINISH GRADE, TOP DRESSED WITH 6-INCHES OF 50/50 COMPOST AMENDED TOPSOIL AND HYDROSEEDED WITH A
- 11. REGULARLY REMOVE ALL PROJECT AND SITE WASTES FROM THE SITE AND PROPERLY DISPOSE OF IN ACCORDANCE WITH ALL APPLICABLE RULES AND REGULATIONS.
- 12. UPON COMPLETION OF PROJECT WORK, ALL WASTE, EQUIPMENT, TOOLS AND MATERIALS NOT INCLUDED FOR RETENTION, SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH ALL APPLICABLE RULES AND
- 13. KEEP PARK DRIVES, PARKING AREAS, ACCESS ROADS AND PUBLIC
- 14. UPON COMPLETION OF WORK, CLEAN (JET WASH AND VACTOR CLEAN) ONSITE STORM CATCH BASINS AND PIPES.
- 15. TESC MEASURES SHOWN ARE APPROXIMATE. AUGMENT, REPAIR, REPLACE OR OTHERWISE MODIFY MEASURES AS NEEDED TO COMPLY WITH KING COUNTY REQUIREMENTS. MEASURES MAY ALSO BE REALIGNED AND MODIFIED TO ACCOMMODATE WORK ACTIVITIES AND WORK PROGRESS, PROVIDED ALL REQUIREMENTS ARE MET.

### TESC AND DEMOLITION KEY NOTES

- 1 INSTALL INLET PROTECTION ON EXISTING CATCH BASINS
  - (2) EXCAVATE TO EXPOSE EXISTING FIELD UNDERDRAIN SYSTEM PIPES. VERIFY CLEANLINESS AND FUNCTION. CLEAN AND REPAIR AS NECESSARY IN PREPARATION FOR USE OF INTACT AND PROPERLY FUNCTIONING PORTIONS TO BE INTEGRATED INTO THE RENOVATED AND FINAL UNDERDRAIN SYSTEM.
  - (3) PROTECT ALL EXISTING FIELD LIGHTS AND POWER SUPPLY ITEMS. (TYP.)
  - (4) PROTECT ALL PAVEMENT TO REMAIN.

  - 12) REMOVE EXISTING ALL-WEATHER FIELD MATERIAL (ESTIMATED TO BE 10-INCHES MINIMUM) TO TOP OF DRAINAGE SYSTEM.

# TESC, CLEARING & DEMO LEGEND

	SHEET C2.1
—— x —⑤F— x ——	SILT FENCE, DETAIL #4, SHEET C2.1
	TEMPORARY FENCE, DETAIL #3, SHEET C2.1
	INLET PROTECTION, DETAIL #1, SHEET C2.1
©1)	CLEARING LIMITS
	TREE PROTECTION, DETAIL #7, SHEET C2.1
$\boxtimes$	TREE REMOVAL
	STAGING AREA WITH TEMPORARY FENCE

**DEM** RD ∞ REDMOND

CONVERSION

11/30/2012


© DOWLHKM 2013


CALL 48 HOURS **BEFORE YOU DIG** 1-800-424-5555




- 4. MORE SUBSTANTIAL (CHAIN LINK) FENCING SHALL BE INSTALLED IF TEMPROARY FENCE FAILS TO PREVENT ENCROACHMENTS IN TO AREAS NOT TO BE DISTURBED.
- 3. CLEARING FENCE TO BE USED AT CLEARING LIMITS UPHILL OF CONSTRUCTION LIMITS. CLEARING FENCE TO BE USED AT CLEARING LIMITS UPHILL OF CONSTRUCTION LIMITS.


- 2. WIRE FENCE TO STEEL FENCE POST.

















RETRIEVAL STRAP


- 3. SEDIMENT REMOVAL SHALL BE ACCOMPLISHED BY REMOVING THE INSERT, EMPTYING, AND RE-INSERTING IT INTO THE CATCH BASIN.
- 2. SEDIMENT SHALL BE REMOVED FROM THE UNIT WHEN IT BECOMES HALF FULL.
- PLACEMENT OF A NEW CATCH BASIN.
- 1. INSERT SHALL BE INSTALLED PRIOR TO CLEARING AND GRADING ACTIVITY, OR UPON
- SEDIMENT ACCUMULATION NOTES:
- -OVERFLOW BYPASS FOR PEAK STORM GEOTEXTILE FABRIC VOLUMES

ADAPTOR SKIRT TRIM TO WITHIN 3" - 5" OF GRATE


# **INTERCEPTOR SWALES & DIKES**


DAMAGE RESULTING FROM RUNOFF OR CONSTRUCTION ACTIVITY SHALL BE REPAIRED IMMEDIATELY. IF THE FACILITIES DO NOT ADEQUATELY INTERCEPT AND CHANNEL STORM RUNOFF, THE CAPACITY AND OR FREQUENCY SHALL BE REVISED.







PER WSDOT STD. PLAN I-4







- 4. PERFORM MAINTENANCE IN ACCORDANCE WITH STANDARD SPECIFICATIONS 8-01.3(9)A AND 8-01.3(15).
- 2. INSTALL SILT FENCING ALONG CONTOURS WHENEVER POSSIBLE. 3. INSTALL THE ENDS OF THE SILT FENCE TO POINT SLIGHTLY UP-SLOPE TO PREVENT SEDIMENT FROM FLOWING AROUND THE ENDS OF THE FENCE.
- 1. MAXIMIZE DETENTION OF STORMWATER BY PLACING FENCE AS FAR AWAY FROM THE TOE OF SLOPE AS POSSIBLE WITHOUT ENCROACHING ON SENSITIVE AREAS OR OUTSIDE OF THE CLEARING BOUNDARIES.
- NOTES:



DISCHARGE TO STABILIZED CONVEYANCE, OUTLET OR

NOTE: TRAP MAY BE FORMED BY BERM OR BY PARTIAL OR COMPLETE EXCAVATION

1' MIN. DEPTH OVERFLOW SPILLWAY

TRAP OUTLET

2. ANY DAMAGE TO THE TRAP EMBANKMENTS FOR SLOPES SHALL BE REPAIRED.

1. 6-FT. HIGH TEMPORARY CHAIN LINK FENCE SHALL BE PLACED AT 5' BEYOND THE DRIPLINE

2. WORK WITHIN PROTECTION FENCE SHALL BE DONE MANUALLY. NO STOCKPILING OF MATERIALS, VEHICULAR TRAFFIC, OR STORAGE OF EQUIPMENT OR MACHINERY SHALL BE

ALLOWED WITHIN THE LIMIT OF THE FENCING.

TREE PROTECTION

OF THE TREE TO BE SAVED. FENCE SHALL COMPLETELY ENCIRCLE THE TREE(S). INSTALL

FENCE POSTS USING PIER BLOCKS ONLY. AVOID DRIVING POSTS OR STAKES INTO MAJOR

4. MINIMUM SURFACE AREA IS 1315 SQUARE FEET AT ELEVATION 600

3. TRAP OUTLET MAY NOT BE NEEDED ON THIS PROJECT.

SEDIMENT TRAP

1. SEDIMENT SHALL BE REMOVED FROM THE TRAP WHEN IT REACHES 1 FOOT IN DEPTH.

NATIVE SOIL OR '

COMPACTED BACKFILL

GEOTEXTILE <

SEDIMENT TRAP NOTES

CROSS-SECTION

MIN. 1' DEPTH

MIN. 1' DEPTH 4"-1.5" WASHED GRAVEL

6-FT MIN

**CALL 48 HOURS** 

**BEFORE YOU DIG** 

1-800-424-5555

2"-4" ROCK


LEVEL SPREADER


REVISIONS	DESCRIPTION	11/30/12 PERMIT SUBMITTAL			
	DATE	11/30/12			
	REV				


Ш 11/30/201 © DOWLHKM 201

S


SHEET







1 CONCRETE FIELD CURB SECTION ADJACENT TO PAVEMENT




CONCRETE FIELD CURB SECTION ADJACENT TO LANDSCAPING

N.T.S.

## FIELD AND SITE CURB NOTES


- 1. EXTERIOR EDGES MAY BE 3/4" CHAMFER
- 2. INTERIOR EDGE (FIELD TURF SIDE) SHALL BE TOOLED RADIUS
- 3. GRIND SMOOTH ALL CURB EDGES. REMOVE ALL BURRS, TABS AND OTHER ROUGH PROTRUSIONS.



3 FIELD CURB AT FENCE POST PLAN DETAIL N.T.S.

# STANDARD CONCRETE NOTES

- 1. F'c = 4000 PSI FOR ALL CONCRETE UNLESS OTHERWISE NOTED. 2. ULTIMATE STRENGTH DESIGN METHOD SHALL BE USED. SUBMIT MIX DESIGN AND DATA.
- 3. MAXIMUM WATER-CEMENT RATIO BY WEIGHT SHALL BE 0.46 FOR AIR-ENTRAINED CONCRETE. MIXING AND PLACING OF ALL CONCRETE, AND SELECTION OF MATERIALS SHALL BE IN ACCORDANCE WITH THE IBC AND ACI CODE 318.
- 4. PROPORTION AGGREGATE TO CEMENT RATIO TO PRODUCE A DENSE WORKABLE MIX WITH 4" MAXIMUM SLUMP, WHICH CAN BE PLACED WITHOUT SEGREGATION OR EXCESS FREE SURFACE WATER. SEE SPECIFICATIONS FOR ADMIXTURES.
- 5. PROVIDE  $5\% \pm 0.5\%$  TOTAL AIR CONTENT FOR CONCRETE EXPOSED TO FREEZING AND THAWING EXPOSURES.
- 6. LIMIT WATER-CEMENT RATIO TO 0.45 AND USE TYPE V CEMENT WHERE CONCRETE IS EXPOSED TO SOIL CONTAINING WATER SOLUBLE SULFATE IN EXCESS OF 0.2%. ADD NO WATER AT SITE.
- 7. WATER REDUCING OR SUPERPLASTICIZING ADMIXTURES MAY BE USED TO INCREASE WORKABILITY WITHOUT INCREASING WATER—CEMENT RATIO OF DESIGN MIX SUBMITTAL.
- 8. SEE SPECIFICATIONS FOR CURING 3/4" CHAMFER ALL EXPOSED CONCRETE EDGES UNLESS INDICATED OTHERWISE ON ARCHITECTURAL DRAWINGS.



4 STANDARD CONCRETE PAVEMENT SECTION

REV DATE DESCRIPTION 11/30/12 PERMIT SUBMITTAL

B Kedmond, Washington 98052 www.dowlhkm.com



PO BOX 107, REDMOND, W 98073-0107

VIL DETAILS & NOTES RIDGE FIELD CONVERSION

13427.0°

© DOWLHKM 2013


SHEET


C4.3


CALL 48 HOURS


BEFORE YOU DIG


1-800-424-5555











SCALE: 1"=20' H, 1"=5' V

CALL 48 HOURS **BEFORE YOU DIG** 

13427.0 11/30/2012 PROJECT DATE © DOWLHKM 2013 SHEET C5.3 1-800-424-5555

POTTE AGUE

Reduced M

SION

CONVER

 $\Box$ 


RIDGE

STORM


RE

**PROFILES** 

DRAINAGE



**EXISTING DRAIN REHABILITATION** 



1. USE A MINIMUM OF A 54 IN. DIAM. TYPE 2 CATCH BASIN.

- 2. OUTLET CAPACITY: 100-YEAR DEVELOPED PEAK FLOW.
- 3. METAL PARTS: CORROSION RESISTANT. NON-GALVANIZED PARTS PREFERRED. GALVANIZED PIPE PARTS TO HAVE ASPHALT TREATMENT 1.
- 4. FRAME AND LADDER OR STEPS OFFSET SO:
- A. CLEANOUT GATE IS VISIBLE FROM TOP; B. CLIMB-DOWN SPACE IS CLEAR OF RISER AND CLEANOUT GATE;
- C. FRAME IS CLEAR OF CURB.
- 5. IF METAL OUTLET PIPE CONNECTS TO CEMENT CONCRETE PIPE, OUTLET PIPE TO
- HAVE SMOOTH O.D. EQUAL TO CONCRETE PIPE I.D. LESS 1/4 IN.
- 6. PROVIDE AT LEAST ONE 3 X 0.090 GAUGE SUPPORT BRACKET ANCHORED TO CONCRETE WALL WITH 5/8 IN. STAINLESS STEEL EXPANSION BOLTS OR EMBEDDED SUPPORTS 2 IN.
- INTO M/H WALL (VERTICAL SPACING).
- 7. LOCATE ELBOW RESTRICTOR(S) AS NECESSARY TO PROVIDE MIN. CLEARANCE AS SHOWN.
- 8. LOCATE ADDITIONAL LADDER RUNGS IN STRUCTURES USED AS ACCESS TO TANKS OR VAULTS TO ALLOW ACCESS WHEN CATCH BASIN IS FILLED WITH WATER.

	- 6" INLET
8" OUTLET	
	OTE: MINIMUM STANCE IS 2'
NTS	TANGE 13 Z
8" OUTLET - 137.62"	
8" OUTLET 137.62	─ 6" INLET
	OTE: MINIMUM STANCE IS 2'
NTS	
6" OUTLET	└─ 6" INLET
	OTE: MINIMUM
NTS 8" OUTLET	
	8" INLET
	OTE: MINIMUM STANCE IS 2'
NTS	2 13 2


NTS	
6" OUTLET	6" INLET
	*NOTE: MINIMUM
CB RESTRICTOR #3	DISTANCE IS 2'
NTS	
8" OUTLET — a — *	
22.4.*	✓ 8" INLET
	<b>&gt;</b>
CB RESTRICTOR #4	*NOTE: MINIMUM DISTANCE IS 2'
NTS	DISTANCE IS 2
1410	

NIMUM	RECTANGULAR WEIR
IS 2'	ANGLE (H) NOTCH ELEVATION ( SECTION
	V-NOTCH WEIR

— NOTCH ELEVATION (F)

<u>PLAN</u>


CB RESTRICTOR #	CB RIM ELEV. (A) (IN FEET)	INLET IE (B) (IN FEET)	OUTLET IE (C) (IN FEET)	ORIFICE Ø (D) (IN INCHES)	RISER RIM ELEV. (E) (IN FEET)	WEIR (TYPE)	NOTCH ELEV. (F) (IN FEET)	NOTCH LENGTH, L (G) (INCHES)	NOTCH ANGLE (FOR (BEGREES)
CB RESTRICTOR #1	600.24	593.68	593.68	0.91	594.50	RECTANGULAR	594.20	2	N/A
CB RESTRICTOR #2	600.62	594.45	594.45	0.81	595.27	V-NOTCH	594.95	N/A	65
CB RESTRICTOR #3	595.38	590.80	590.80	0.75	591.62	V-NOTCH	591.25	N/A	45
CB RESTRICTOR #4	595.35	589.15	589.15	0.81	589.97	V-NOTCH	589.60	N/A	45




SITE SPECIFIC DATA REQUIREMENTS VATER QUALITY FLOW RATE (cfs) PEAK FLOW RATE (< 1 cfs) NOTES/SPECIAL REQUIREMENTS CARTRIDGE HEIGHT = 18"

	SIT	E SPEC	CIFIC D	ATA	
	F	REQUIR	EMENT	ſS	
1	STRUCTURE ID			STORM	//FILTER #2
	WATER QUALITY	FLOW RAT	ΓE (cfs)		0.013
	PEAK FLOW RAT	,			0.080
1	RETURN PERIOD	OF PEAK	FLOW (yrs	)	100
1	# OF CARTRIDG	ES REQUIR	RED		1
1	CARTRIDGE FLO	W RATE (I	5 OR 7.5	apm)	7.5
1	MEDIA TYPE (CS	F, PERLITE	E, ZPG)		CSF
1					
l	PIPE DATA:	I.E.	MATERIAL	_  DI/	AMETER
	INLET PIPE # I	594.37	PVC		8"
	INLET PIPE #2	N/A	N/A		N/A
	OUTLET PIPE	591.32	PVC		12"
	RIM ELEVATION				600.58
1	ANTI-FLOTATION	BALLAST	WIDT		HEIGHT
			N/A		N/A
	NOTES/SPECIAL	REQUIREN	MENTS:		
	CARTRIDGE HEI	GHT = 27'	ı		
I	I				


	SIT	E SPEC	CIFI	C DAT	Α	
	F	REQUIR	EM	ENTS		
₹#2	STRUCTURE ID			STO	DRN	1FILTER ;
13	WATER QUALITY	FLOW RAT	ΓE (cfs	5)		0.029
80	PEAK FLOW RAT	E (<   cfs)				0.154
00	RETURN PERIOD	OF PEAK	FLOW	/ (yrs)		100
	# OF CARTRIDGI	ES REQUIR	RED			2
5	CARTRIDGE FLO	W RATE (I	5 OR	7.5 apm	1)	7.5
6F	MEDIA TYPE (CS					CSF
R	PIPE DATA:	I.E.	MAT	ERIAL	DIA	METER
	INLET PIPE # I	584.13	P۱	√C		12"
	INLET PIPE #2	N/A		/A		N/A
	OUTLET PIPE	581.83	P۱	/C		12"
.58	RIM ELEVATION					595.2
1T	1117 5 0717101				_	
1T	ANTI-FLOTATION	BALLAST	\_\	MIDTH	_	HEIGHT
				N/A		N/A
	NOTES/SPECIAL	REQUIREN	1ENTS	ò:		
	CARTRIDGE HEI	GHT = 18'	1			





N.T.S.

**PLAN VIEW** STANDARD OUTLET RISER



	STORMFIL	TER DESI	GN NOTES	<del></del>		
STORMFILTER TREATMENTCAPACITY IS A FUNCTORY OF STYLE IS SHOWN WITH THE MAXIMUM NUMBER OF MANHOLE STORMFILTER PEAK HYDRAULICUS REQUIRED.	OF CARTRIDGES (4).	. VOLUME SYSTE	M IS ALSO AVAILA	BLE WITH MAXIMU	JM 4 CARTRIDGES	
CARTRIDGE SELECTION						
CARTRIDGE SELECTION		7"	1	8"	LOW	DROP
		?7" 05'		8" .3'	LOW 1	
CARTRIDGE SELECTION CARTRIDGE HEIGHT		•		<del>-</del>	<u> </u>	

- **GENERAL NOTES**
- 1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
- 2. DIMENSIONS MARKED WITH ( ) ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY. 3. FOR SITE SPECIFIC DRAWINGS WITH DETAILED VAULT DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH ENGINEERED
- SOLUTIONS LLC REPRESENTATIVE. www.contechES.com 4. STORMFILTER WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS
- 5. STRUCTURE SHALL MEET AASHTO HS20 AND CASTINGS SHALL MEET AASHTO M306 LOAD RATING, ASSUMING GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER
- 6. FILTER CARTRIDGES SHALL BE MEDIA-FILLED, PASSIVE, SIPHON ACTUATED, RADIAL FLOW, AND SELF CLEANING. RADIAL MEDIA DEPTH
- SHALL BE 7-INCHES. FILTER MEDIA CONTACT TIME SHALL BE AT LEAST 39 SECONDS.
- 7. SPECIFIC FLOW RATE IS EQUAL TO THE FILTER TREATMENT CAPACITY (gpm) DIVIDED BY THE FILTER CONTACT SURFACE AREA (sq ft).
- INSTALLATION NOTES 1. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE
- SPECIFIED BY ENGINEER OF RECORD.
- 2. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STORMFILTER STRUCTURE (LIFTING CLUTCHES PROVIDED).
- CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE.
- 4. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET PIPE(S). 5. CONTRACTOR TO PROVIDE AND INSTALL CONNECTOR TO THE OUTLET RISER STUB. STORMFILTER EQUIPPED WITH A DUAL DIAMETER HDPE OUTLET STUB AND SAND COLLAR. IF OUTLET PIPE IS LARGER THAN 8 INCHES, CONTRACTOR TO REMOVE THE 8 INCH OUTLET

STUB AT MOLDED IN CUT LINE. COUPLING BY FERNCO OR EQUAL AND PROVIDED BY CONTRACTOR. 6. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.



STORMFILTERS BY CONTECH

CALL 48 HOURS BEFORE YOU DIG 1-800-424-5555



AINAG DMOND

PROJECT 11/30/201

ш

© DOWLHKM 2013