

King County CSO 5-Year Update

Task 4.0 Development of Alternatives

Brown & Caldwell, K C M,
Herrera Environmental Consultants and Associated Firms

December 1997

CONTENTS

Executive Summary	vii
Alternatives Development	vii
Basis of Sizing and Cost Estimating	viii
CSO Control Project Impacts	ix
Other Issues	x
Introduction	1
RWSP Cross Reference	3
Hydraulic Analysis	5
King County Hydraulic Model	5
West Point Peak Flow Set Point	5
State of Washington CSO Control Regulation Projects	6
Federal CSO Policy Control Projects	6
Onsite CSO Treatment	9
Cost Development	13
Component Cost Estimating	13
Partial Separation Cost Estimates	14
CSO Control Elements: Implementation and Impact	17
Alternatives Development	19
Duwamish CSO Control Alternatives	21
Storage in the Duwamish	21
Separation and Storage in the Duwamish Area	26
Onsite CSO Treatment	27
Local Onsite CSO Treatment Siting Issues	29
Flow Transfer to EDRP at Renton (Southern Transfer)	29
Denny/Lake Union CSO Control Alternatives	31
Centralized Duwamish Area CSO Treatment	33
Assumptions	33
West Seattle and Alki CSOs	33
CSO Treatment Facilities	33
Effluent Disposal	35
CATAD Operations	35
CSO Treatment in Conjunction with Secondary Treatment (Task 5 Group 3b)	35
CSO Treatment Only at Duwamish (Task 5 Group 3c)	37
Southern Service Area Deep Tunnel Storage Alternatives	41

South Magnolia CSO Control Alternatives	43
Storage Alternative	43
Rooftop Separation Alternative	43
North Interceptor Basin.....	47
Deep Tunnel Storage for University, Montlake and 3 rd Avenue West	47
Storage Tank Alternatives	51
University and Montlake.....	51
3 rd Avenue West.....	57
11 th Avenue NW.....	58
Ballard Regulator	59
North Interceptor CSO Treatment Alternatives.....	60
Partial Separation Alternatives	61
University/Montlake	61
Ballard and 11 th Avenue NW (Ballard Basin).....	62
Alki Basin	65
Partial Separation.....	65
Offline Storage.....	65
Offline Storage with Pump Station.....	66
Parallel Conveyance System.....	66
Building Sewer Rehabilitation and Roof Drainage Separation	68
West Seattle Basin	69
Harbor Regulator CSO Control Alternatives.....	69
Conveyance/Storage Alternative.....	69
Separation.....	69
Chelan Regulator CSO Control Alternatives.....	71
Storage in Conjunction with Alki Tunnel	71
Storage in Separate Tank	71
Refinements.....	73
8th Avenue South Regulator CSO Control Alternative.....	73
West Michigan Regulator	75
Terminal 115.....	75
Norfolk Basin.....	81
Martin Luther King Way Overflow.....	82
Storage Alternative.....	82
Separation Alternative.....	82
South Henderson Street Pump Station CSO Control Alternatives	82
Storage Alternative.....	84
Weir Adjustment Alternative	84
Separation Alternative.....	84
Norfolk Regulator CSO Control Alternative.....	84
Norfolk Project Combinations and Cost Estimates	86

TABLES

Table 4-1	Task 4 Document Reference to Task 5 Report.	3
Table 4-3	Unit Partial Separation Project Costs.....	15
Table 4-4	Impacts of CSO Control Technologies.	18
Table 4-5	Duwamish CSOs.....	21
Table 4-6	Duwamish Area CSO Storage Facilities ^a	22
Table 4-7	Industrial Area Separation/Storage Projects.	27
Table 4-8	Duwamish Onsite Treatment: Alternative 1—Vortex Separators.	28
Table 4-9	Duwamish Onsite Treatment: Alternative 2—Rectangular Storage/ Sedimentation Facilities.....	28
Table 4-10	Reduction in Overflows due to Southern Area Transfer to EDRP.	29
Table 4-11	Facility Costs Associated with Flow Transfer to EDRP at Renton.	30
Table 4-12	Costs for Duwamish CSO/Secondary Treatment Alternative.....	37
Table 4-13	Costs for Duwamish CSO Treatment Alternative.	39
Table 4-14	Southern Service Area Deep Tunnel Alternatives.	42
Table 4-15	South Magnolia CSO Control Alternatives.	43
Table 4-16	Existing North Interceptor CSO Conditions.	47
Table 4-17	Summary of North Interceptor CSO Alternatives.....	48
Table 4-18	Increase in CSO Volumes due to New Lake Line.	48
Table 4-19	Project Costs for University, Montlake, 3 rd Avenue W Deep Tunnel Storage.	51
Table 4-20	Summary Descriptions of North Interceptor Storage Tank Alternatives.....	51
Table 4-21	Alternative University/Montlake Storage Tanks.	56
Table 4-22	Project Costs for 3 rd Avenue West Alternatives.....	58
Table 4-23	11 th Avenue NW Storage Alternative Project Costs.	58
Table 4-24	North Interceptor CSO Treatment Facilities.....	60
Table 4-25	Project Costs for North Interceptor CSO Treatment Alternatives.	61
Table 4-26	University/Montlake Separation Alternative Project Costs.....	62
Table 4-27	Ballard Separation Cost Analysis.	62
Table 4-28	Alki Basin CSO Control Alternatives.....	65
Table 4-29	West Seattle CSO Existing Conditions.....	69
Table 4-30	Eighth Avenue S Regulator - Upstream Separation Analysis.....	73
Table 4-31	Eighth Avenue S Regulator - Downstream Separation Analysis.....	74
Table 4-32	West Seattle Basin CSO Control Alternatives.....	77
Table 4-33	Norfolk Basin CSO Existing Conditions.	81
Table 4-34	Norfolk Basin CSO Control Alternatives.	81
Table 4-35	Impact of Return Flows from CSO Storage/Treatment on West Point Design Flows.	92
Table 4-35	Capital Costs to Use West Point Clarifiers for Additional CSO Treatment.....	100

FIGURES

Figure 4-1	Performance of West Point Primary Sedimentation Facilities for Suspended Solids Removal.....	10
Figure 4-2	Kingdome-Industrial Area CSO Storage Sites.....	23
Figure 4-3	Conceptual Layout of Brandon and Michigan CSO Treatment or Storage Sites.....	24
Figure 4-4	Conceptual Layout of King/Connecticut and Hanford/Lander CSO Treatment or Storage Sites.....	25
Figure 4-5	Location of Duwamish Centralized CSO Treatment Facility.....	34
Figure 4-6	Conceptual Layout of South Magnolia CSO Control Storage Alternative.....	45
Figure 4-7	Conceptual Layout of University Regulator to 6 th Avenue West Deep Tunnel CSO Control Alternative.....	50
Figure 4-8	University and Montlake Area Alternative Storage Tank Sites.....	52
Figure 4-9	3 rd Avenue West CSO Control Facilities.....	53
Figure 4-10	Conceptual Layout of CSO Control Storage Alternative at 11 th Avenue NW Weir.....	54
Figure 4-11	Conceptual Layout of City and Metro Ballard CSO Control Storage Alternative.....	55
Figure 4-12	Conceptual Layout for Alki Basin CSO Control Conveyance Storage Alternative.....	67
Figure 4-13	Conceptual Layout for Harbor Avenue CSO Control Conveyance Alternative.....	70
Figure 4-14	Conceptual Layout for Chelan Regulator CSO Control Conveyance Storage Alternative.....	72
Figure 4-15	Total Project Cost as a Function of Additional Partial Separation for 8 th Avenue South.....	74
Figure 4-16	Conceptual Layout of 8 th Avenue South CSO Control Storage Alternative.....	76
Figure 4-17	Conceptual Layout for SW Michigan Street CSO Control Diversion Alternative.....	78
Figure 4-18	Alternative Sites for Terminal 115 CSO Control Storage Tank.....	79
Figure 4-19	Conceptual Layout of Martin Luther King Way CSO Storage Tank.....	83
Figure 4-20	Conceptual Layout of South Henderson Street CSO Control Storage Alternative.....	85
Figure 4-21	Conceptual Layout of Norfolk CSO Control Storage Alternative.....	87
Figure 4-22	Conceptual Layout of North Beach Pump Station Expansion CSO Control Alternative.....	90